



LAWRENCE
LIVERMORE
NATIONAL
LABORATORY

D & D Best Practices Demolition of a Research Facility Building 431

W. L. Collins

October 3, 2005

EFCOG Infrastructure Management Working Group
Livermore, CA, United States
October 4, 2005 through October 6, 2005

Disclaimer

This document was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor the University of California nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or the University of California. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or the University of California, and shall not be used for advertising or product endorsement purposes.

D&D Best Practices Demolition of a Research Facility Building 431



**William L. Collins, P.E.
SAT Project Manager
Lawrence Livermore National Laboratory**

**EFCOG – Infrastructure Management Working Group
October 4-6, 2005**


UCRL-PROC-215810

This work was performed under the auspices of the U.S.
Department of Energy by University of California, Lawrence
Livermore National Laboratory under Contract W-7405-Eng-48.

Overview of best practices



- Single program supports planning and facility disposition
- Facility information gathering leads to comprehensive PEP
- Clearly defined scope
- Resource loaded schedule allows tracking of earned value
- Design-demo Acquisition results in best schedule and cost
- Integrated Project Team avoids problems
- Risk factors retired
- Continuous Environment, Safety & Health oversight
- Comprehensive UG utility location prevents incidents
- Color coding of systems communicates hazards
- Field execution photos



Facility disposition supports strategic objectives




One Integrated Program for both Institutional S&M and D&D

- 1. Provide facility management for buildings that are surplus or excess to Program needs.**
 - **Manage the process to transition facilities from an operating condition into an inactive status**
- 2. Plan and execute facility disposition in support of strategic objectives.**
 - **The Space Action Team (SAT) is an integrated multi-disciplinary, multi-directorate, cross-trained team with diverse talents and skills dedicated to execute facility projects**
- 3. This approach increases flexibility and value**
 - **Supports programs through relief of unneeded facilities**
 - **Provides flexibility in establishing project priorities**
 - **Utilizes S&M as a precursor to disposition**
 - **Establishes a balance to optimize utilization of surplus facilities**




The Laboratory's flexible approach to manage its disposition program begins with the end in mind



Stabilizing & Removing Excess/Surplus Facilities is a Key Element to Strategic Facility Planning



160 Real Property Structures
~ 410k GSF (+ 90k SF yard space)
~ 500k GSF to completion...



● Facilities demolished/removed FY94—01

■ Facilities for demo in FY02


Institution “owns” 50 buildings,
~800k SF excess/re-assignable space.

- Single program responsibility supports “Dual Purpose” planning
- Provides a framework for decision making and priority setting
- Supports “End Point Planning” starting at initiation of transfer
- B431 is a good example of this efficiency

Recycle stats:
Concrete – 22,000 Tons
Metal – 2,400 Tons
Freon – 1,300 lbs
Wood – 180 CY



Facility information process for D&D



Historical Search Table of Contents



Facility

- Master Equipment List (MEL)
- Phone and networks
- Asbestos
- High pressure data base
- Key plans
- Facility number changes
- Maintenance backlog
- Deficiencies
- Facility photos
- Historical Site Maps
- FIMS

General

- Personal Interviews
- E-mails
- IAS and ORs
- Sunflower Report
- Archives
- Security
- Store Room
- Financial Records

Environmental & Hazards


- Drain Reports
- EPD file review
- Chem track
- Spill Reports
- Environmental Permits
- SWPPP
- Retention Tank Reports
- Waste Records
- NEPA/NHPA
- Screening report/H.A.R.
- Facility Haz. Class
- H. C. Team facility files
- Fire Dept. files
- RAD Survey 10 CFR 835
- HEPA filter data base

***The facility status and historical data
supports a successful PEP and is
archived with a project closeout report.***



- **Constructed 1950**
- **Material Test Accelerator program**
- **Mirror Fusion Test Facility**
- **ETA-II, a non-nuclear facility, remains operational**





No.	Date	Revision	Drawn	Checked	By	For
1						
Lawrence Livermore National Laboratory Plant Engineering, Livermore, CA 94550						
BUILDING 431 DEMOLITION						
FIRST FLOOR DEMOLITION PLAN						
Des: VEIBI YUAN	17/31/03	Scale:				
Draw: VEIBI YUAN	19/03/03	PN:				
Check:		S/A:				
Draw No:	PLA2003-0431-0003D	Sheet No:	A-1			



Scope of work



- Isolation and reroute of utilities to minimize neighborhood impact
 - Temporary re-routing of 13.8 KV circuit and removal inside pit
 - Replace transformer and re-route main feeders to ETA
 - Reroute elec circuits and piping feeding nearby buildings
- Remove concrete shield block (35T) Depleted Uranium target wall
- Abate Asbestos Containing Material (e.g., exterior siding, flooring, lead paint, thermal system insulation, etc.)
- Remove and dispose of interior and exterior equipment
- Demolish steel structure – 100' hibay roof, 50T crane, 4 story structure
- Demolish North concrete shield wall and foundation to grade level
- Backfill pit
- Rebuild and weatherproof South roof and siding

Alternatives evaluated and various reviews conducted throughout the life of a project.





Management systems, controls and planning




- Once Authorized, the Integrated Project Team plans, manages and controls the project using a tailored approach of DOE Order 413.3 and the Project Management Manual, DOE M413.3-1.
- The LLNL Space Action Team has management responsibility for the day-to-day work execution
- Implementing documents
 - NNSA FIRP⁽¹⁾ Program Execution Plan
 - LLNL FIRP Program Management Plan
 - LLNL ISMS Implementation Plan
 - Building 431 Project Execution Plan
- Special project reviews
 - Independent Project Review at Critical Decision 0
 - External Independent Review at Critical Decision 1/2/3
 - Value Engineering “Red Team” led by a certified Project Management Professional (PMP)
- Resource loaded schedule used to track work scheduled and performed, and compared to actual costs to establish monthly earned value
- Monthly schedule and cost performance is tracked at Division Level (WBS Level 2) and reported externally to NNSA at Level 1
- NNSA Livermore Site Office (LSO) oversight

CD - 0 Mission Need – Plan & Prep
CD - 1 Alternative Selection – “DEMOLITION”
CD - 2 Performance Baseline - “TPC \$12M, Completion Nov. 2006”
CD - 3 Begin Field Demolition Activities
CD - 4 Project Completion and Closeout

Good communication eliminates surprises.



Project performance reporting



Schedule Variance Recovery Plan:

None required.

Highlights and Lowlights

- ◆ LO/GSE utility deactivation contractor substantially complete at 96%; life safety systems and punchlist remaining in Aug and temp power removal in Sep.
- ◆ ETA major electrical outage for refeed of power successfully completed; ETA equipment back on-line.
- ◆ Continued site support activities: sampling of concrete for recycle and oil for waste disposal.
- ◆ Completed review of demolition subcontract (Evans Brothers Inc.) submittals; resubmit some items in response to comments.
- ◆ Abatement/Demo NTP granted July 21; EBI/Bayview mobilized July 28 and began abatement preparations.
- ◆ Abatement activities were started in July on removal of Galbestos siding. [Abatement Start Milestone]
- ◆ Two transforms with PCB oil need processed as hazardous waste; other oil needs pumped by approved waste hauler.
- ◆ Superblock security camera installation complete and cameras deactivated and removed from B431.
- ◆ NNSA granted approval for 48 property items to be disposed by the demo subcontractor; tags have been removed.
- ◆ Specs and procurement package for roof/wall restoration being delayed to review high construction estimate and evaluate alternate go-forward plan; no impact on critical path.
- ◆ Perspective of Roof Restoration completed.
- ◆ B431 SCR (describing two segments) has been signed by the AB group and PAT ADFM, then submitted to LSO for formal review.
- ◆ Developed Critical Lift Plan for removal of Depleted Uranium Shield Block. Final approval expected in September to execute work.

Safety Minute

- ◆ Deactivation of all mechanical and electrical systems complete (except Life Safety) in preparation for demo.
- ◆ Some final color coding still needs worked by H&ST and Construction Inspector.

Key Milestones

Utility Deactivation Start	Jan-05	✓
Award Demolition Contract Start	May-05	✓
Abatement Start	Jul-05	✓
Demolition Start	Sep-05	
CD-4 Project Complete	Nov-06	

Several reports help monitor performance.



Acquisition Strategy



- Finalized after CD-0 and submitted per DOE M 413.3-1
- Combination of LLNL staff and competitive fixed-price procurements awarded by the University of California. Assumptions:
 - LLNL staff handles prep work, sampling, hazardous waste disposal, ES&H oversight and PM
 - LLNL Labor-only contractor (Davis-Bacon) performs utility isolation and re-routing
 - Design-demolition (“Design / Unbuild”) subcontract awarded hazards abatement, demolition, backfill, and site grading. Experience & safety record essential.
 - Design-build subcontract will be awarded for weatherproofing and repair/rebuild of the remaining roofing and siding.
- Detailed design-demolition specifications and detailed utility deactivation drawings and procedures prepared
- Design-demo subcontract strategy resulted in several different demolition approaches
 - Best value bid uses method not originally considered
 - Recycle value \$250k and 85% of materials
- Best value evaluation: license & certifications, security, vibration, traffic, recycle, schedule, safety history (ERR & TRR), shield wall demo, similar projects, references and price.

***Design-demo process results in
best schedule and cost.***



Integrated project team (IPT) involvement



- ETA-II, a non-nuclear facility, remains operational and continues experiments
- Computations server facility and archive records management facility B439
- High voltage routing through existing building
- Machine shop services facility B432
- Operational Security Plan due to the proximity to security area
 - Vehicle and personnel access
 - Staging of material and equipment
 - Restrictions on crane size, placement, accessibility and relocation
 - Security related work stoppages may impact the project
- ES&H Teams
- Representative personnel are on the project review team

***IPT participation avoids problems
during execution.***



Risk and Contingency Management



- Risk Management Plan developed, risk assessment completed and a risk mitigation strategy prepared.
- The activities with the highest risks are Electrical & Mechanical Isolation, shield wall removal and Renovation.
- The high risk factors include:
 - Encountering stored energy
 - ETA II sensitivity to vibration
 - Difficulty with demolition of the shield wall due to its size
 - Schedule uncertainty due to uniqueness of shield wall demo, potential weather delays, impacts to nearby operational facilities, ETA operational status

Plan updated as risk factors retired.



Environmental, Safety and Health



- Environmental, Safety and Health incorporated into the planning
- Historical operational background reviews and surveys to determine likely hazards and contamination levels
- NEPA review performed and the project granted a categorical exclusion
- NHPA review performed and the building determined to be of no historical significance to the State of California.
- Confirmatory sampling performed for ACM in order to better bound the scope of abatement
- Integrated Safety Management System – DOE Seven Guiding Principles and Five Core Functions
 - Integrated Worksheet (IWS) defining scope, hazards, controls, training and authorizing the work
 - Subcontractor Site specific Health & Safety Plan and Corporate Injury & Illness Prevention Program

***Continuous safety oversight and
managed review of concerns.***




Utility safety is best served by integrating historical information and active measurements



RECONCILE COLOR KEY

GREEN	MAP/LOCATOR CONCUR
PURPLE	MAP/LOCATOR CONCUR - UTILITY TYPE DISCREPANCY
ORANGE	HISTORICAL MAP ID/LOCATOR CANNOT FIND
PINK	LOCATOR FOUND/NOT IN HISTORICAL MAPS

Nondestructive excavation



GPR/GPS and Acoustic Listening Device



Radio frequency device traces line

Marker balls



Color Coding Best Practice



Problem: Decommissioning systems containing stored energy or contaminants is a communication challenge. Tracking materials from sample through resolution, protective of workers and the environment requires constant verification and documentation to properly control through release.

Solution: SAT uses a color code to identify the status of all Structures, Sub-systems, and Components (SSCs) during decommissioning through disposition.

Red: Known hazard exists on or inside a SSC.

Yellow: SSCs denoting caution.

Blue: Controlled disposal to the Municipal Landfill

Green: Free release - no issue.

Black: Editorials and instructions



Field Execution




- Completed
 - Deactivation and reroute of utilities
 - Interior abatement
 - Demolition of 8,000 SF



Field Execution



Field Execution



- **Working**
 - Abatement/removal of Galbestos siding
 - Structural demo
 - Specs for Restoration design-build



Restoration planning for Design-build



D&D best practices



- Single program supports S&M and D&D
- Resourced schedule tracks performance
- Design-demo acquisition achieved best schedule/ cost
- Integrated Project Team eliminates surprises
- Environment, Safety & Health team participation
- Comprehensive UG utility location - ZERO hits
- Color coding of systems clearly communicates hazards

Embracing best practices sustains team performance and achieves mission success.

