



LAWRENCE
LIVERMORE
NATIONAL
LABORATORY

National Ignition Facility Control and Information System Operational Tools

C. D. Marshall, R. G. Beeler, G. A. Bowers, R. W.
Carey, J. M. Fisher, C. B. Foxworthy, T. M. Frazier, D.
G. Mathisen, L. J. Lakin, J. J. Rhodes, M. J. Shaw

October 14, 2009

12th International Conference on Accelerator and Large
Experimental Physics Control Systems
Kobe, Japan
October 12, 2009 through October 16, 2009

Disclaimer

This document was prepared as an account of work sponsored by an agency of the United States government. Neither the United States government nor Lawrence Livermore National Security, LLC, nor any of their employees makes any warranty, expressed or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States government or Lawrence Livermore National Security, LLC. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States government or Lawrence Livermore National Security, LLC, and shall not be used for advertising or product endorsement purposes.

NATIONAL IGNITION FACILITY CONTROL AND INFORMATION SYSTEM OPERATIONAL TOOLS

C. D. Marshall, R. G. Beeler, G. A. Bowers, R. W. Carey, J. M. Fisher, C. B. Foxworthy, T. M. Frazier, D. G. Mathisen, L. J. Lagin, J. J. Rhodes, M. J. Shaw

Lawrence Livermore National Laboratory, P.O. Box 808, Livermore, California USA

Abstract

The National Ignition Facility¹⁻⁹ (NIF) in Livermore, California, is the world's highest-energy laser fusion system and one of the premier large scale scientific projects in the United States. The system is designed to setup and fire a laser shot to a fusion ignition or high energy density target at rates up to a shot every 4 hours. NIF has 192 laser beams delivering up to 1.8 MJ of energy to a ~2 mm target that is planned to produce >100 billion atm of pressure and temperatures of >100 million degrees centigrade. NIF is housed in a ten-story building footprint the size of three football fields as shown in Fig. 1. Commissioning was recently completed and NIF will be formally dedicated at Lawrence Livermore National Laboratory on May 29, 2009. The control system has 60,000 hardware controls points and employs 2 million lines of control system code. The control room has highly automated equipment setup prior to firing laser system shots. This automation has a data driven implementation that is conducive to dynamic modification and optimization depending on the shot goals defined by the end user experimenters. NIF has extensive facility machine history and infrastructure maintenance workflow tools both under development and deployed. An extensive operational tools suite has been developed to support facility operations including experimental shot setup, machine readiness, machine health and safety, and machine history. The following paragraphs discuss the current state and future upgrades to these four categories of operational tools.

EXPERIMENTAL SHOT SETUP

Experiments are setup in a web based Campaign Management Tool (CMT) that allows end use principal investigators to define facility technical goals with a high degree of flexibility. For example, a full 192 beam NIF shot with targets and diagnostics contains approximately 10,000 experimental input definitions required for automated machine setup prior to firing a shot such as laser energies or target diagnostic aim points. These can be defined in grouped blocks or down to the individual component level at the discretion of the principal investigator. This experimental input deck then flows through analysis tools to define derived setup parameters and verify that machine safety limits are not exceeded. At this point the experiment is electronically "ready" to be conducted. Prior to beginning the shot, analysis can then be performed on the facility readiness to conduct this

experiment (physical configuration) and schedule optimization can be performed to minimize the maintenance impact of performing this experiment. When the experimental shot setup process is started, the shot cycle setup model is dynamically defined through turning on and off approximately 20,000 macrosteps, or pieces of automated work scope, that define the shot cycle setup model. This dynamic model functionality is designed to optimize the operational execution of the shot cycle. The shot setup process flow and examples of the tools which perform the facility readiness analysis, optimization, and results visualization will be presented.

MACHINE READINESS

Once an experimental shot setup is defined, the facility physical and commissioning readiness can be assessed against the current status of the facility. This collection of web based tools is essential for the facility operations team to have an effective means of evaluating the next steps in reconfiguring the facility for the next experiment. The central element of this system is the Configuration Checker which takes the experimental plan converts it to physical configuration requirements and compares it to the installation and commissioning status of the facility. Both general and specific physical configurations are verified. For example if a special user optic is required, then the required optic part number and installation orientation is compared to that installed in the facility. From there a list of discrepancies is generated for operations which is graphically displayed as go, no go for shot for each beamline. Drill down capability, to required facility reconfigurations, and list generation of required work scope is automated. NIF consists of more than 6,000 Line Replaceable Units (LRUs) that within a group or type can be interchangeably replaced for ease of maintenance. The installation and commissioning status of LRUs is color coded and graphically displayed on a standard beaming format which is organized by LRU type and location. In addition to LRU readiness there is a Restriction Manager which records and classifies any operational restrictions which may be placed by the engineering or operations organizations on a functional sub-system or component. Restrictions are categorized by type which includes conditional use, do not use, or out of service for maintenance. Restrictions are further categorized by location in the system which implies which laser beamlines and beam end use locations are affected. Conditional use restrictions contain additional information about temporary energy and power

limitations that are below the full performance envelope of the machine. An automated algorithm compares the experimental shot requirements with these categorized restrictions to produce a list of any restrictions that apply to the planned experiment.

MACHINE HEALTH AND SAFETY

NIF has performed an extensive Failure Modes and Effects Analysis that has defined machine safety control points or devices in the system. These devices have specific machine safety requirements, such as required position, reservations and verifications at shot time. Virtually all critical devices are automatically positioned and verified by the shot cycle control software, but it was determined that an independent engineered status verification method was required that adds an additional layer of protection given the complexity of the NIF system. This status verifier system directly interrogates the device level control hardware separate from supervisory or status and control aggregation levels and compares their positions and status with a predetermined set of device requirements that is independent derived with simplified logic from shot setup requirements. The status of this verification is provided in a rolled up graphical format with drill down capability to the device level. Higher level processes such as closed loop alignments or voltage profile monitoring are fed to a central alerts framework and displayed by an Alerts Manager. This alerts manager categorizes the alerts by subsystem and provides a mechanism for retaining, acknowledging, and clearing alerts. This provides flexibility to operations to monitor in an organized way for alerts that are new, latent, and false alarms. Examples of these machine health and safety applications will be presented and discussed.

MACHINE HISTORY

NIF has provided for an extensive machine history archiving and data visualization of component level history. The Machine History Database includes the Shot Setup requirements, change management history of those requirements, optics damage inspection, and laser diagnostics archive. This data is available to be visualized with a web based suite of GUIs that organizes and displays the information both in raw format as well as processed or analyzed. This is achieved by archiving of device positions or capturing images on every shot and plotting the long term trending of device data for facility

predictive maintenance. In addition, the long term trending of subsystem efficiency or performance is recorded as part of the shot control framework. The duration of macrosteps are measured and recorded for each of shots conducted on the facility. The analysis of these trends and blocks allows for optimization of the shot cycle or machine turn on model as facility conditions evolves.

ACKNOWLEDGMENTS

The authors would like to thank all the dedicated personnel working on NIF and on Integrated Computer Control Systems and Shot Data Systems specifically. This work was performed under the auspices of the U.S. Department of Energy by Lawrence Livermore National Laboratory under Contract DE-AC52-07NA27344.

REFERENCES

- [1] Moses, E. et al, "The National Ignition Facility Update," Int'l Conf. on Fusion Sciences and Appl., San Francisco, California, September 2009.
- [2] Moses, E. et al, "The National Ignition Facility: Path to Ignition in the Laboratory," Int'l Conf. on Fusion Sciences and Appl., Biarritz, France, September 2005.
- [3] Van Arsdaal, P. et al, "Status of the National Ignition Facility and Control System" 10th ICALEPCS, Geneva Switzerland, October 2005.
- [4] Ludwigsen, P. et al, "Software Engineering Processes Used to Develop the NIF Integrated Computer Control System", 11th ICALEPCS, Knoxville, TN USA, October 2007.
- [5] Lagin, L. et al, "Shot Automation for the National Ignition Facility, 10th ICALEPCS, Geneva Switzerland, October 2005.
- [6] Wilhelmsen, K. et al, "Automatic Alignment System for the National Ignition Facility", 11th ICALEPCS, Knoxville Tennessee, October 2007.
- [7] Carey, R. et al, "The National Ignition Facility Data Repository", 12th ICALEPCS, Kobe Japan, October 2009.
- [8] Azevedo, S. et al, "Automated Experimental Data Analysis at the National Ignition Facility", 12th ICALEPCS, Kobe Japan, October 2009.
- [9] C A Haynam *et al* 2008 *J. Phys.: Conf. Ser.* **112** 032004 (7pp)




Figure 1: The National Ignition Facility (NIF) at the Lawrence Livermore National Laboratory (LLNL) in Livermore California is the world's first megaJoule laser facility now conducting experiments for the National Ignition Campaign.